

SHIP REPAIR DIVISION

M/V INVESTIGATOR



Main Particulars

Type: DRILLING SHIP

IMO: 8020795 LOA x B : 59,40 x 14

> GRT: 1.306 DWT: 1.129 Flag: Vanuatu

R.Owner: Geoquip Marine Operations AG (Switzerland)
T.Manager: Geoquip Marine Operations AG (Switzerland)
Operator: Geoquip Marine Belgium BVBA (Switzerland)

Arrival: 22/09/2016 Departure: 08/11/2016

SHIP REPAIR REPORT

SCOPE OF WORKS CARRIED OUT Reference: RE01619

- * Docking / undocking and provision of general services for repair works.
- * Hull treatment works: HP washing of underwater area, scraping of underwater area, top sides blasting SA 2 in spots; application of one touch up on underwater area and two touch up coats on top sides; application of two full coats on underwater area and one full coat on top sides.
- * Repainting of boundary line
- * Painting of marks, names, scales, symbols.
- * Anchor and chains: Lowering, marking, HP washing; chains calibration; anchor and chains painting.
- * Chain lockers: Removal of mud, cleaning and painting with two coats.
- * Renewal of anodes on external shell
- * Tailshaft. Measure and report tailshaft clearance.
- * Tailshafts. Withdrawal for Class Survey Inspection.
- * Overhauling of sterntube seals in workshop
- Supply and installation of new intermediate shaft bearings
- * Removal rudder blades and rudder stocks for replacing rudder stock bushes, machining new sleeves
- * Overhauling of both steering gears cylinders, renewal of seals.
- * Dismounting propeller blades of port side for replacing the seals.
- Overhauling of sea valves
- * Cleaning, washing and painting seachest and seachest grids
- * Ultrasonic cleaning of 13 box coolers at workshop.
- * Renewal of steel in fore peak tank, mud tank of port and starboard side,
- * and within tank nº 6.
- * Replace anchor cable
- Renewal of pipes of different systems.