

M/V PERTUSOLA



Main Particulars

Type: LPG TANKER

IMO: 9147394

LOA x B : 145,28 x 22

GRT: 12.800

DWT: 17.670

R.Owner: CARBOFIN Spa (Italy)

T.Manager: CARBOFIN Spa (Italy)

Operator: CARBOFIN Spa (Italy)

Arrival: 22/11/2016

Departure: 12/12/2016

SHIP REPAIR REPORT

SCOPE OF WORKS CARRIED OUT

Reference: RE01617

- * Docking / undocking and provision of general services for repair works.
- * **Hull treatment:** HP washing, blasting Sa 2 of underwater area and top sides, in spots, touch up painting (2 coats) of blasted areas, application of 1 full coat.
- * Painting of marks, symbols, letters, draft scales, plimsoll discs, etc
- * Anchor and chains lowering, chains calibration, HP washing and painting.
- * Cleaning of chain lockers.
- * Renewal of cathodic protection.
- * Tail shaft poker measurement. Stern tube seals renewal.
- * Yard's assistance on intermediate shaft bearing maintenance works.
- * Rudder stock and pintle measurement. Rudder pressure test.
- * Yard's assistance on steering gear maintenance works.
- * Propeller blasting and painting with silicon paint.
- * Overhauling of valves.
- * Yard's assistance on cargo safety valves overhauling.
- * Renewal of 75 m of cargo pipe insulation.
- * Renewal of huge amount of seamless carbon steel pipes on deck.
- * Renewal of some fuel oil, vent pipe and sea water cooling pipes on main deck.
- * Full overhauling and maintenance works on hydraulic windlass winches.
- * Overhauling of 10 electric motors .
- * Ventilation ducts renewal.
- * Renewal of 3 tons of steel grade DH36 in double bottom tanks 12 and 13.
- * Top mast steel repairs.
- * Yard's assistance to Service Engineer for Cargo Tank Domes
- * Roller fairleads: Removing freeing, measuring, inspecting, refitting and greasing of single roll fairleads.